



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-179-20267-00-01

RECEIVED
STATE CORPORATION COMMISSION
JUN 21 1971
CONSERVATION DIVISION
Wichita, Kansas

06-21-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Wasinger of Knight Casing Pulling Co., Inc. has this date requested permission to plug the following described well:

Mr. Wasinger guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Mickey Well No. 1

Location: NE
NW-NE-NE Sec. 12 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 4068' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Wasinger was instructed to plug the well as follows:

249'---8 5/8" Surface casing, cement circulated.
4065'---4 1/2" Production casing cemented on bottom with 200 Sx. No plug back nor perforations indicated.

Sand well back to 4040' and set 3 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 30 sacks gel and 135 Sx. cement, staged.

Very truly yours,

K. S. Nichols
Conservation Division Agent