



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 17 1971
CONSERVATION DIVISION
Wichita, Kansas
05-17-1971

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20282-00-00

Dear Sir:

Mr. Bill Draper of Dreiling Oil, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Don E. Pratt,

Complete Address: Drawer #370, Hays, Kansas.

Lease Name: Mickey Well No. 2

Location: NE-NW-NE Sec. 12 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 3849' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Draper was instructed to plug the well as follows:

249'--8 5/8" Surface casing, cement circulated with 165 Sx.
Top of Dakota section @ 975'.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. G. Daniels
Conservation Division Agent