

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20052-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 6 1961
11-06-1961
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Don Favinger of Murfin Drilling Company has this date requested permission to plug the following described well:

Mr. Favinger guarantees payment of the plugging fee.

Operator's full Name: Nadel and Gussman,

Complete Address: 625 Union Center, Wichita, Kansas.

Lease Name: Eberle Well No. 1

Location: Ad: CNE-NW Sec. 17 Twp. 9 Rge. (E)(W) 27

County Sheridan Total Depth 4100 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Favinger was instructed to plug the well as follows:

231'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Dakota section from 1200' to 1040'.

Circulate hole with heavy mud. Pull DP to 1220' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent