



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

AUG 7 1972
CONSERVATION DIVISION
Wichita, Kansas
08-07-1972

15-179-20318-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Marion Burris of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Burris guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: J. Meyers Well No. 1

Location: App:-Se-NW-NW Sec. 18 Twp. 9 Rge. (E)(W) 27

County: Sheridan Total Depth 3387' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burris was instructed to plug the well as follows:

224'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota section @ 1225'.

Circulate hole with heavy mud. Pull DP to 1450' and displace 110 Cu. Ft. cement thru DP. Pull DP to 240' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent