



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 5 1973
CONSERVATION DIVISION
Wichita, Kansas
#303-05-1973

15-179 - 20168-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Russ Sullivan of Russ Casing Pulling, Inc., has this date requested permission to plug the following described well:

Mr. Sullivan guarantees payment of the plugging fee.

Operator's full Name: Dreiling Oil, Incorporated,

Complete Address: R. R. #2, Victoria, Kansas.

Lease Name: Ochs Well No. 1

Location: SE-SW-SW Sec. 13 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4185' Oil Well X

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Sullivan was instructed to plug the well as follows:

280'--8 5/8" Surface casing, cement circulated.
4106'--4 1/2" Production casing cemented on bottom with 150 Sx. No plug back indicated. Top of perforations @ 3912'.

Push plug to 3875', sand back to 3850' and set 4 Sx. cement with dump bailer. Pull 4 1/2" casing and squeeze well with 5 sacks hulls, 35 sacks gel and 150 Cu. Ft. cement, staged.

Very truly yours,

W. L. Nichols
Conservation Division Agent