

State of Kansas



ROBERT B. DOCKING Governor  
DALE E. SAFFELS Chairman  
JULES V. DOTY Commissioner  
JAMES O. GREENLEAF Commissioner  
RAYMOND B. HARVEY Secretary  
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 17 1969  
CONSERVATION DIVISION  
Wichita, Kansas

04-17-1969

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-179-20195-00-00

Dear Sir:

Mr. Jack Ensminger of American Drilling Co., Inc., has this date requested permission to plug the following described well:

Mr. Ensminger guarantees payment of the plugging fee.

Operator's full Name: Glen Rupe and American Drilling Company, Inc.

Complete Address: 222 Brown Building, Wichita, Kansas.

Lease Name: Ochs Well No. B-1

Location: NW-SW-SE Sec. 13 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4170' Oil Well

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Ensminger was instructed to plug the well as follows:

241'--8 5/8" Surface casing, cement circulated with 175 Sx.  
Top of Dakota section @ 1275'.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.  
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent