



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
APR 29 1968
CONSERVATION DIVISION
Wichita, Kansas

04-29-1968

15-179-20089-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Leo J. Dreiling Oil Company,

Complete Address: Victoria, Kansas.

Lease Name: Dunham & Goeckler Well No. 1

Location: NW-NW-SW Sec. 22 Twp. 9 Rge. (E)(W) 28

County: Sheridan Total Depth 4200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Zorn was instructed to plug the well as follows:

24'--8 5/8" Surface pipe, cement circulated with 175 Sx.
Top of Dakota section @ 1225'.

Circulate hole with heavy mud. Pull DP toll 50' and displace 100 Sx.
cement thru DP. Pull DP to 240' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. S. Nichols
Conservation Division Agent