



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
 500 Insurance Bldg. 212 N. Market
 WICHITA, KANSAS 67202

RECEIVED
STATE CORPORATION COMMISSION

SEP 18 1968

CONSERVATION DIVISION
Wichita, Kansas

09-18-1968

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20133-00-00

J. P. Roberts
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Koch Exploration Company,

Complete Address: Box #2256, Wichita, Kansas.

Lease Name: Patmon Well No. 1

Location: SE-NE-SW Sec. 5 Twp. 9 Rge. (E)(W) 29

County: Sheridan Total Depth 4230' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

231'--8 5/8" Surface pipe, cement circulated with 210 Sx.
Top of Dakota section @ 925'.

Circulate hole with heavy mud. Pull DP to 1150' and displace 100 Sx.
cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent