



ROBERT B. DOCKING Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
DALE E. SAFFELS Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-179-20107-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
JUN 10 1968
CONSERVATION DIVISION
Wichita, Kansas
06-10-1968

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Rock Island Oil & Refining Company,

Complete Address: 321 West Douglas, Wichita, Kansas.

Lease Name: Johnson Well No. B-1

Location: SE-SE-SE Sec. 8 Twp. 9 Rge. (E)(W) 29

County: Sheridan Total Depth 4195 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

258'--8 5/8" Surface pipe, cement circulated.
Top of Dakota Section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Picheli
Conservation Division Agent