



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
NOV 9 1970
CONSERVATION DIVISION
Wichita, Kansas

11-09-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20275-00-00

Dear Sir:

Mr. Leo Lindenmuth of Chief Drilling Company, Inc., has this date requested permission to plug the following described well:

Mr. Lindenmuth guarantees payment of the plugging fee.

Operator's full Name: Chief Drilling Company, Incorporated,

Complete Address: 905 Century Plaza, Wichita, Kansas.

Lease Name: Sloan Well No. 1

Location: CS/2-SW-NE Sec. 8 Twp. 9 Rge. (E)(W) 29

County: Sheridan Total Depth 3865 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Lindenmuth was instructed to plug the well as follows:

252'--8 5/8" Surface casing, cement circulated with 170 Sx.
Top of Dakota Section @ 1300.

Circulate hole with heavy mud. Pull DP to 1500' and displace 100 Sx.
cement thru DP. Pull DP to 270' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. L. Dehals
Conservation Division Agent