



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
 500 Insurance Bldg. 212 N. Market  
 WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
 (To Be Filed By Plugging Agent)

15-179-20131-00-00

RECEIVED  
 STATE CORPORATION COMMISSION  
 SEP 6 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 09-06-1968

J. P. Roberts  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Bill Draper of Gabbert & Jones, Incorporated has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Koch Exploration Company,

Complete Address: Box #2256, Wichita, Kansas.

Lease Name: Bange Well No. 1

Location: SW-NE-NW Sec. 17 Twp. 9 Rge. (E)(W) 29

County: Sheridan Total Depth 2550 Oil Well

Gas Well  Input Well  6WD Well  D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

26 1/2" --- 8 5/8" Surface pipe, cement circulated with 200 Sx.  
Top of Dakota section @ 800'.

Circulate hole with heavy mud. Pull DP to 1180' and displace 100 Sx.  
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

M. L. Nichols  
 Conservation Division Agent