



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 11 1969
CONSERVATION DIVISION
Wichita, Kansas
09-11-1969

15-179-20228-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Mike Mikelson of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Mikelson guarantees payment of the plugging fee.

Operator's full Name: Kaiser-Francis.

Complete Address: 909 Palace Building, Tulsa, Oklahoma.

Lease Name: Pratt #1. Well No. 1

Location: APP; CNW-SW Sec. 36 Twp. 9 Rge. (E)(W) 29

County: Sheridan Total Depth 4026 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Mikelson was instructed to plug the well as follows:

273'--8 5/8" Surface casing, cement circulated with 175 Sx.

Circulate hole with heavy mud. Pull DP to 1200' and displace 100 Sx. cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

A. L. Nichols
Conservation Division Agent