

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-193-20011-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORP COMMISSION
MAR 17 1969
CONSERVATION DIVISION
Wichita, Kansas

03-17-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Trend Exploration, Limited

Complete Address: 600 Capitol Life Building, Denver, Colorado.

Lease Name: _____ Page _____ Well No. 1

Location: _____ CSW-SE _____ Sec. 16 Twp. 9 Rge. (E)(W) 33

County: Thomas Total Depth 4740' Oil Well _____

Gas Well _____ Input Well _____ SWD Well _____ D & A X Lost Hole _____

Mr. Parks was instructed to plug the well as follows:

278'--8 5/8" Surface casing, cement circulated with 200 Sx.
Top of Dakota section @ 1550'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

H. F. Nichols
Conservation Division Agent