



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

15-193-20026-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
DEC 22 1969
CONSERVATION DIVISION
Wichita, Kansas
12-22-1969

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Trend Exploration, Limited,

Complete Address: 600 Capital Life Building, Denver, Colorado.

Lease Name: Nye Well No. 1

Location: CNW-NW Sec. 16 Twp. 9 Rge. (E)(W) 32

County: Thomas Total Depth 4688' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

271'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1525'.

Circulate hole with heavy mud. Pull DP to 1775' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent