



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
APR 21 1972  
04-21-1972  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-163-20427-00-00

Dear Sir:

Mr. Freeman of SAGE Drilling  
Garvey Drig. has this

date requested permission to plug the following described well:

Mr. Freeman guarantees payment of the plugging fee.

Operator's full Name: L. H. Pearsom

Complete Address: 603 Union Center Bldg., Wichita, Ks.

Lease Name: Roy Lindquist Well No. 1

Location: SE SE SE Sec. 21 Twp. 10 Rge. (E)(W) 16

County: Rooks Total Depth 3715' Oil Well

Gas Well  Input Well  SWD Well  D & A XX Lost Hole

Mr. Freeman was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 725' and displace

110 cu ft cmt thru drill pipe. Heavy mud to 185' set cementing plug

and displace 30 cu ft cmt thru drill pipe. Heavy mud to 40' set

cementing plug, 1/2 sk hulls and 10 Cu Ft cmt to base of cellar.

Very truly yours,

Geo F. Marsup  
Conservation Division Agent