

State of Kansas



15-163-30017-00-00

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY O. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

RECEIVED
STATE CORPORATION COMMISSION

Dear Sir:

Mr. Moore of C-G Drilling Company has this AUG 4 1966

date requested permission to plug the following described well 08-04-1966

Mr. Moore guarantees payment of the plugging fee. Wichita, Kansas

Operator's full Name: C - G Drilling Company

Complete Address: 107 Rule Bldg., Wichita, Kansas

Lease Name: Rea Ziegler Well No. 1

Location: SE SW Sec. 21 Twp. 10 Rge. 16 (E) (W) X

County Rooks Total Depth 3721 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Moore was instructed to plug the well as follows:

Gun pits, circulate Heavy mud, set cementing plug at 540 Ft.

and displace 20 sc cement thru drill pipe. Heavy mud to 200 Ft.

set cementing plug and displace 20 sc cement thru drill pipe.

Heavy mud to 40 Ft. set cementing plug, 1/2 sc hulls and 10 sc

cement to base of celler. Plug rat hole with 2 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent