

State of Kansas



WM. H. AVERY Governor
WILLIAM L. MITCHELL Chairman
JAMES O. GREENLEAF Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-163-30220-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 13 1966
10-13-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Administrator
500 Insurance Building
Wichita 2, Kansas

Dear Sir:

Mr. Harre of Thoroughbred Drlg. Co. has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company

Complete Address: 502 Ritz Bldg., Tulsa, Oklahoma

Lease Name: Cecil Masters "C" Well No. 1

Location: C SE NE Sec. 25 Twp. 10 Rge. 16 (E)(W) X

County Rooks Total Depth 3697' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

Gun pits, circulate heavy mud, set cementing plug at 540' and displace 25 sc cement thru drill pipe. Heavy mud to 240' set cementing plug and displace 20 sc cement thru drill pipe. Heavy mud to 40' set cementing plug, 1/3 sc hulls and 10 sc cement to base of cellar. Plug rat hole with 2 sc cement.

Very truly yours,

Leo Massey
Conservation Division Agent