

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20170-00-00

RECEIVED
STATE CORPORATION COMMISSION
DEC 24 1968
CONSERVATION DIVISION
Wichita, Kansas
12-24-1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Meier Well No. 1

Location: SE-NW-SE Sec. 1 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4250' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

318'--7" OD Surface casing, cement circulated with 115 Sx. (6 1/4" Hole).
Top of Dakota section @ 1375'.

Circulate hole with heavy mud. Pull DP to 1600' and displace 60 Sx.
cement thru DP from 1600' to 1300'. Pull DP to 335' and displace 15 Sx.
cement thru DP from 335' to 260'. Pull DP, set bridge @ 40' with 1/2 sack
hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent