

State of Kansas



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

15-179-20167-00-00

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

DEC 16 1968

CONSERVATION DIVISION
Wichita, Kansas

12-16-1968

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center Building, Wichita, Kansas.

Lease Name: Calverley Well No. 1

Location: CNW-NE Sec. 2 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4285' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

329'--7" Od Surface casing, cement circulated with 100 Sx. (6 1/4" Hole).
Top of Dakota section @ 1425'.

Circulate hole with heavy mud. Pull DP to 1650' and displace 60 Sx.
cement thru DP. Pull DP to 360' and displace 15 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

W. D. Nichols

Conservation Division Agent