

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

# State Corporation Commission

## CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

**VERBAL PERMIT FORM**  
 (To Be Filed By Plugging Agent)

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 1 1 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas  
 12-11-1968

15-179-20163-00-00

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Tom Buffington of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Buffington guarantees payment of the plugging fee.

Operator's full Name: Norman D. Fitzgerald,

Complete Address: Box #5046, Abilene, Texas.

Lease Name: R. R. Morgan Well No. 1

Location: SW-NE Sec. 8 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4311 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Buffington was instructed to plug the well as follows:

232'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1300'.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx. cement thru DP. Pull DP to 245' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

*M. L. Pichela*

Conservation Division Agent