



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 27 1970
CONSERVATION DIVISION
Wichita, Kansas
05-27-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-179-20251-00-00

Dear Sir:

Mr. Bill Draper of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Draper guarantees payment of the plugging fee.

Operator's full Name: Shields Oil Producers, Incorporated,

Complete Address: Shields Building, Russell, Kansas.

Lease Name: Schiltz Well No. 1

Location: NW SW-NE Sec. 9 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4280' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Draper was instructed to plug the well as follows:

294'--8 5/8" Surface casing cement circulated with 210 Sx.
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1575' and displace 100 Sx.
cement thru DP. Pull DP to 310' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. L. Nichols
Conservation Division Agent