



ROBERT B. DOCKING Governor
 DALE E. SAFFELS Chairman
 JULES V. DOTY Commissioner
 JAMES O. GREENLEAF Commissioner
 RAYMOND B. HARVEY Secretary
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-179-20200-00-00

RECEIVED
 STATE CORPORATION COMMISSION
 APR 17 1969
 CONSERVATION DIVISION
 Wichita, Kansas

04-17-1969

J. Lewis Brock
 Administrator
 500 Insurance Building
 Wichita, Kansas 67202

Dear Sir:

Mr. Sylvester Fickel of Red Tiger Drilling Company, has this date requested permission to plug the following described well:

Mr. Fickel guarantees payment of the plugging fee.

Operator's full Name: Koch Exploration Company,

Complete Address: P. O. Box #2256, Wichita, Kansas.

Lease Name: Wiggington Well No. 1

Location: CNE-SE Sec. 13 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4200 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Fickel was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated with 185 Sx.
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

N. L. Fickel
 Conservation Division Agent