

State of Kansas



ROBERT B. DOCKING Governor
DALE E. SAFFELS Chairman
JULES V. DOTY Commissioner
JAMES O. GREENLEAF Commissioner
RAYMOND B. HARVEY Secretary
JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAY 5 1969
CONSERVATION DIVISION
Wichita, Kansas

05-05-1969

15-179-20201-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Charles Harre of Broken Arrow Drilling Co., has this date requested permission to plug the following described well:

Mr. Harre guarantees payment of the plugging fee.

Operator's full Name: National Associated Petroleum Company,

Complete Address: Fourth Floor Petroleum Building, Tulsa, Oklahoma.

Lease Name: Geo. Boeger Community Well No. A-1

Location: CSW-NW Sec. 32 Twp. 9 Rge. (E)(W) 30

County: Sheridan Total Depth 4945 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Harre was instructed to plug the well as follows:

268'--8 5/8" Sur face casing, cement circulated with 150 Sx.

Circulate hole with heavy mud. Pull DP to 1525' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sacks cement to bottom of cellar.

Very truly yours,

Conservation Division Agent