



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 21 1970
CONSERVATION DIVISION
Wichita, Kansas
09-21-1970

15-193-20033-00-00

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated.

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Schwartz Well No. 2

Location: CNE-SW Sec. 1 Twp. 9 Rge. (E)(W) 31

County: Thomas Total Depth 4098' Oil Well

Gas Well Input Well SWD Well D & A Lost Hole

Mr. Hunt was instructed to plug the well as follows:

288'--8 5/8" Surface casing, cement circulated with 225 Sx.
Top of Dakota section @ 1325'.

Circulate hole with heavy mud. Pull DP to 1550' and displace 100 Sx.
cement thru DP. Pull DP to 300' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

M. S. Nichols
Conservation Division Agent