



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-193-20039-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
FEB 16 1972  
CONSERVATION DIVISION  
Wichita, Kansas

02-16-1972

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Art Hunt of Rains & Williamson Oil Co., has this date requested permission to plug the following described well:

Mr. Hunt guarantees payment of the plugging fee.

Operator's full Name: Lewis M. Mull,

Complete Address: 415 Page Court, 220 West Douglas, Wichita, Kansas.

Lease Name: Johnson Well No. 1

Location: CE/2-NE-SW Sec. 3 Twp. 9 Rge. (E)(W) 31

County: Thomas Total Depth 4315' Oil Well     

Gas Well      Input Well      SWD Well      D & A X Lost Hole     

Mr. Hunt was instructed to plug the well as follows:

286'--8 5/8" Surface casing, cement circulated with 200 Sx.  
Top of Dakota section @ 1000'.

Circulate hole with heavy mud. Pull DP to 1225' and displace 110 Cu. Ft.  
cement thru DP. Pull DP to 310' and displace 30Cu. Ft. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to  
bottom of cellar.

Very truly yours,

*W. L. Nichols*  
Conservation Division Agent