



ROBERT B. DOCKING
DALE E. SAFFELS
JULES V. DOTY
JAMES O. GREENLEAF
RAYMOND B. HARVEY
JACK GLAVES

Governor
Chairman
Commissioner
Commissioner
Secretary
Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
SEP 30 1968
CONSERVATION DIVISION
Wichita, Kansas
09-30-1968

15-193-20005-00-00

J. P. Roberts
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Bill Walker of Rains & Willianson Oil Co., Inc. has this date requested permission to plug the following described well:

Mr. Walker guarantees payment of the plugging fee.

Operator's full Name: Mull Drilling Company, Incorporated,

Complete Address: 1625 Wichita Plaza Building, Wichita, Kansas.

Lease Name: Spadaro Well No. 1

Location: CSE-NW Sec. 4 Twp. 9 Rge. (E)(W) 31

County: Thomas Total Depth 4360' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Walker was instructed to plug the well as follows:

250'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1580' and displace 100 Sx.
cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent