



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian
WICHITA, KANSAS 67217

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

15-193-20044-00-00

RECEIVED
STATE CORPORATION COMMISSION
OCT 30 1972
CONSERVATION DIVISION
Wichita, Kansas
10-30-1972

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Norman Cook of Abercrombie Drilling, Inc., has this date requested permission to plug the following described well:

Mr. Cook guarantees payment of the plugging fee.

Operator's full Name: Abercrombie Drilling, Incorporated,

Complete Address: 801 Union Center, Wichita, Kansas.

Lease Name: Evans Well No. 1

Location: NW-NE Sec. 5 Twp. 9 Rge. (E)(W) 31

County: Thomas Total Depth 4325' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cook was instructed to plug the well as follows:

260'--8 5/8" Surface casing, cement circulated with 175 Sx.
Top of Dakota section @ 1450'.

Circulate hole with heavy mud. Pull DP to 1675' and displace 110 Cu. Ft. cement thru DP. Pull DP to 280' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

W. L. Nichols
Conservation Division Agent