



JOHN ANDERSON, Jr. Governor
WILLIAM L. MITCHELL, Chairman
ALVIN F. GRAUERHOLZ Commissioner
HARRY G. WILES Commissioner
RAYMOND B. HARVEY Secretary
ROBT. C. LONDERHOLM Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)
500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION

MAR 24 1966
03-24-1966
CONSERVATION DIVISION
Wichita, Kansas

J. P. Roberts
Adminstrator
500 Insurance Building
Wichita 2, Kansas

15-193-30024-00-00

Dear Sir:

Mr. C. L. Miles of Miles Drilling Company has this

date requested permission to plug the following described well:

Alfred Ainsworth
Mr. Miles guarantees payment of the plugging fee.

Operator's full Name: Alfred Ainsworth,

Complete Address: 715 4th National Bank Bldg., Wichita, Kansas.

Lease Name: Chase Well No. 1

Location: CSW-SW-SW Sec. 5 Twp. 9 Rge. (E) (W) 33

County Thomas Total Depth 4850 Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Miles was instructed to plug the well as follows:

292'--8 5/8" Surface pipe, cement circulated with 225 Sx.

Circulate hole with heavy mud, set plug @ 600' and 20 Sx. cement.

" " 280' with 1/2 sk. hulls & 20 Sx. cement.
" " 40' with 1/2 sk. hulls & 10 Sx. cement.

Very truly yours,

W. A. Nichols
Conservation Division Agent