



ROBERT B. DOCKING Governor  
WILLIAM L. MITCHELL Chairman  
JAMES O. GREENLEAF Commissioner  
DALE E. SAFFELS Commissioner  
RAYMOND B. HARVEY Secretary  
E. EDWARD JOHNSON Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)  
500 Insurance Bldg. 212 N. Market  
WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-193-20003-00-00

RECEIVED  
STATE CORPORATION COMMISSION  
JUN 27 1968  
CONSERVATION DIVISION  
Wichita, Kansas  
06-27-1968

J. P. Roberts  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

Dear Sir:

Mr. Vernon Zorn of L. J. Dreiling & Sons, Inc., has this date requested permission to plug the following described well:

Mr. Zorn guarantees payment of the plugging fee.

Operator's full Name: Winwell 1968 Exploration Company.

Complete Address: 1011 Commercial National Bank Bldg., Ehrevoport, La.

Lease Name: Herbel Well No. 1

Location: NE-NE-NE Sec. 25 Twp. 9 Rge. (E)(W) 33

County: Thomas Total Depth 4725 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Zorn was instructed to plug the well as follows:

312'--8 5/8" Surface pipe, cement circulated with 265 Sx.  
Top of Dakota section @ 1560'.

Circulate hole with heavy mud. Pull DP to 1785 and displace 100 Sx.  
cement thru DP. Pull DP to 335 and displace 20 Sx. cement thru DP.  
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom  
of cellar.

Very truly yours,

Conservation Division Agent