



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM
(To Be Filed By Plugging Agent)

RECEIVED
STATE CORPORATION COMMISSION
MAR 9 1970
CONSERVATION DIVISION
Wichita, Kansas
03-09-1970

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

15-193-20027-00-00

Dear Sir:

Mr. Clem Burton of Pickrell Drilling Company, has this date requested permission to plug the following described well:

Mr. Burton guarantees payment of the plugging fee.

Operator's full Name: Pickrell Drilling Company,

Complete Address: 705 Fourth National Bank Building, Wichita, Kansas.

Lease Name: Ross Well No. A-1

Location: CNE-SW Sec. 25 Twp. 9 Rge. (E)(W) 33

County: Thomas Total Depth: 4877' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Burton was instructed to plug the well as follows:

330'--8 5/8 " Surface casing, cement circulated with 220 Sx.
Top of Dakota section @ 1350'.

Circulate hole with heavy mud. Pull DP to 1800' and displace 100 Sx.
cement thru DP. Pull DP to 330' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

N. J. Nichols
Conservation Division Agent