



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg. 212 N. Market
WICHITA, KANSAS 67202

VERBAL PERMIT FORM (To Be Filed By Plugging Agent)

15-193-20038-00-00

RECEIVED
STATE CORPORATION COMMISSION
NOV 29 1971
CONSERVATION DIVISION
Wichita, Kansas

J. Lewis Brock
Administrator
500 Insurance Building
Wichita, Kansas 67202

Dear Sir:

Mr. Carl Cheekwood of U. S. Signal Oil & Gas Co., has this date requested permission to plug the following described well:

Mr. Cheekwood guarantees payment of the plugging fee.

Operator's full Name: U. S. Signal Oil & Gas Company-1971 Program,

Complete Address: 125 Central Building, Midland Texas.

Lease Name: Signal '71 Penney Well No. 1

Location: NE-NE Sec. 31 Twp. 9 Rge. (E)(W) 36

County: Thomas Total Depth 5680' Oil Well

Gas Well Input Well SWD Well D & A X Lost Hole

Mr. Cheekwood was instructed to plug the well as follows:

454'--8 5/8" Surface casing, cement circulated with 275 Sx.
Top of Dakota @ 1670' (Electric Log)

Circulate hole with heavy mud. Pull DP to 1925 and displace 115 Sx.
Cement thru DP. Pull DP to 475' and displace 25 Sx. cement thru DP.
Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom
of cellar.

Very truly yours,

Conservation Division Agent