

4-13 4-061066

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20,662-00-00
6'N. & 6'W. of
NW SE NW /4 SEC. 03, 09 S, 31 W
3636 feet from S section line
3636 feet from E section line

Operator license# 5003 Lease Schmidt B Well # 1-3

Operator: McCoy Petroleum Corporation County: Thomas 153.08

Address: 3017 N. Cypress Street Well total depth 4710 feet
Wichita, Kansas 67226-4003 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 319 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Sweetman Drilling, Inc. License# 5658

Address: Wichita, Kansas 67202

Company to plug at: Hour: 10:00 A.M. Day: 13 Month: April Year: 1997

Plugging proposal received from: Brad Fortz

Company: Sweetman Drilling Company Phone: _____

Were: Order 200 sxs 60/40 posmix - 6% gel with 1/4# floseal per sack.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All[], Part[], None[]


Completed: Hour: 12:30 P.M., Day: 13, Month: April, Year: 1997

Actual plugging report:
1st. Plug at 2650' w/25 sxs. Anhydrite 2614' - 2685'.
2nd. Plug at 1750' w/100 sxs. Dakota 1445' - 1745'.
3rd. Plug at 375' w/40 sxs. Surface pipe 319'.
4th. Plug at 40' w/10 sxs.
15 sxs in rathole.
10 sxs in mousehole.

Rec'd
04-23-1997
1997 APR 23 AM 11 02
KANSAS CORP COMM
RECEIVED

Remarks: Allied Cementing.
Condition of casing(in hole): GOOD BAD _____ Anhy.plug: YES NO _____
Bottom plug(in place): YES _____, CALC _____, NO Dakota plug: YES NO _____
Plugged through TUBING _____, CASING _____ Elevation: 2995 GL

I did did not observe the plugging.


(agent)
Form CP-2/3

INVOICED
DATE 4-24-97
INV. NO. 48007
4-13