

9-25

414 R

6 031171

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,470-60-00
C NW SW, SEC. 30, T 9 S, R 31 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 3506

Operator: Nye Exp Inc.
Name & Address: 803 N. Sheridan Suite 1200
Wichita, Kansas 67203

1980 feet from S section line
4620 feet from E section line

Lease Name Englehardt Well # 1

County Thomas 142.68

Well Total Depth 4390 feet

Conductor Pipe: Size _____ feet

Surface Casing: Size 8 5/8 feet 274 w/175 sks

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ U&A

Other well as hereinafter indicated _____

Plugging Contractor Abercrombie Drilling License Number 5422

Address Wichita, Ks.

Company to plug at: Hour: P.M. Day: 25 Month: Sept Year: 19 88

Plugging proposal received from Tony

(company name) Abercrombie (phone) _____

were: 8 5/8" set at 274' w/175 sks. Circ hole w/no less than 36 vis mud
w/no loss or gain of fluid. Keep hole full and balance plugs w/mud. Order
190 sks 60/40 Poz 6% Gel 3% C.C. B. J. Titan Cement Co.

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None

Operations Completed: Hour: 5:30PM Day: 2 5 Month: Sept Year: 19 88

ACTUAL PLUGGING REPORT Spot plug w/drill pipe at 2650' w/25 sks

RECEIVED STATE CORPORATION COMMISSION

1800' w/100 sks and Hulls
325' w/40 sks
40' w/10 sks

NOV 8 1988
11-08-1988
CONSERVATION DIVISION
Wichita, Kansas

15 sks in rathole.

Remarks: Elev. 3057' Anhy 2622' - 66'
(If additional description is necessary, use BACK of this form.)

INVOICED
I, _____, did not observe this plugging.

Signed Carl Goodrow (TECHNICIAN)
Carl Goodrow

DATE 11-9-88
INV. NO. 22966