

5-12-88

6 070682

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,463 -00-00
NE NE SW SEC. 31, T 9 S, R 31 (W/E)
2310 feet from S section line
2970 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4656

Lease Name Engelhardt Well # C 1

Operator: Davis Petroleum Inc.

County Thomas 153.40

Name & Address Route 1 Box 183 B

Well Total Depth 4720 feet

Great Bend, Ks. 67530

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 368

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X

Other well as hereinafter indicated _____

Plugging Contractor L.D. Dreiling Inc. License Number 6039

Address Great Bend, Ks. 67530

Company to plug at: Hour 12:00PM Day: 12 Month: May Year: 19 88

Plugging proposal received from Greg Davidson

(company name) L. D. Drilling Inc. (phone) _____

were: 8 5/8" 368' s.p. cwc w/190 sks cement. 60/40 Poz 2% Gel 3% Ca Cl. By Allied

Cement. Elv 3047'. Anh 2610'. No circulation problems. Mud condition weight

9.5; Viscosity 46; Water loss 8; Proposal 200 sks 60/40 Poz 6% Gel. Spot with

drill stem. Circulate heavy mud between all plugs. 25 sks at 2620'. 100 sks

at 1790' - 50 sks at 400' - 10 sks at 40' - 15 sks rat hole (circulate)

Plugging Proposal Received by Marion J. Schmidt (TECHNICIAN)

Plugging Operations attended by Agent?: All y Part _____ None _____

Operations Completed: Hour 1:45PM Day: 12 Month: May Year: 19 88

ACTUAL PLUGGING REPORT Ordered 200 sks 60/40 Poz 6% Gel 3% Ca Cl and 8 5/8" plug.

Spotted with drill stem. Circulated heavy mud between all plugs.

1st plug at 2620' w/25 sks cement. 2nd plug at 1790' w/100 sks cement

3rd plug at 400' w/50 sks cement. 4th plug Hulls and plug at 40' w/10 sks cement

15 sks in rathole (circulate) Cemented by Allied Cement Co.

RECEIVED
STATE CORPORATION COMMISSION
JUN 20 1988
06-20-1988
CONSERVATION DIVISION
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form.)

(did / x) observe this plugging.

INVOICED

Signed Marion J. Schmidt (TECHNICIAN)

Marion J. Schmidt

DATE 6-29-88

INV. NO. 21106