

11-09
4-050179

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,617-00-00
NW NW NW /4 SEC. 31, 09 S, 31 W
4950 feet from S section line
4950 feet from E section line

Operator license# 5285 Lease Engelhardt well # 1

Operator: Dane G. Hansen Trust County Thomas

Address: P.O. Box 187 Well total depth 4403 feet ^{143.10}
Logan, Kansas 67646 Conductor Pipe: inch @ feet
(913) 689-4816 Surface pipe 8 5/8 inch @ 291 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Allied Cementing License#

Address:

Company to plug at: Hour: pm Day: 09 Month: November Year: 1993

Plugging proposal received from: Harold Dinkel

Company: Chief Drilling Company phone:

Were: Spot plugs through drill pipe w/ heavy mud between all plugs.

1st plug @ 2645 feet with 25 sacks Rat hole: 15 sacks

2nd plug @ 1800 feet " 100 " Mousehole: 10 sacks

3rd plug @ 340 feet " 40 "

4th plug @ 40 feet " 10 with 8 5/8" wiper plug

Plugging Proposal Received by: Marvin L. Miller

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:00 pm, Day: 09, Month: November, Year: 1993

Actual plugging report: Hole reported plugged as above.
Order 200 sx 60/40 pozmix w/ 6% gel and 1/4# celloflake or flowcel per sk

RECEIVED
STATE CORPORATION COMMISSION

Remarks: Elevation: 3053, Anhydrite: 2623-2665 feet, Anhydrite plug: 2645
Bottom plug (in place): Yes X, Calc , No Arbuckle: None
NOV 24 1993
CONSERVATION DIVISION
Wichita, Kansas

Did NOT penetrate Arbuckle, cemented by Allied Cementing Company

I did[] / did not[X] observe the plugging. Marvin Miller

Marvin L. Miller P.I.R.T.II
(agent)

Form CP-2/3

INVOICED
DATE 12-3-93
INV. NO. 39343