

4-11

262 R

6 031356

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API NUMBER 15- 193-20-512-00-00

W/2 SE SE, SEC. 32, T 9 S, R 31 W/4E

TECHNICIAN'S PLUGGING REPORT

Operator License # 3372

Operator Name: Morrison Dixon Oil Oper Inc.
Address: 100 N. Main Suite 801
Wichita, Ks. 67202

660 feet from S section line

990 feet from E section line

Lease Name Ostmeyer Well # A #1

County Thomas 152.75

Well Total Depth 4700 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 267

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Murfin Drilling Co. License Number 6033

Address Wichita, Ks.

Company to plug at: Hour: PM Day: 11 Month: April Year: 19 90

Plugging proposal received from Lloyd

(company name) Murfin Drilling (phone)

were: 8 5/8 set at 267 w/170 sks cwc. Circ hole w/no less than 36 vis mud
w/no loss or gain of fluid. Keep hole full of and balance plugs w/mud.

Order 190 sks 60/40 poz 6% gel 3% cc 8 5/8 w.p. Allied Cement Co.

Plugging Proposal Received by Carl (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None x

Operations Completed: Hour: 4:30PM Day: 11 Month: April Year: 19 90

ACTUAL PLUGGING REPORT Spot plugs w/drill pipe at 2625 w/25 sks

1850' w/100 sks and hulls.

320' w/40 sks

40' w/10 sks w.p. circ 15 sks rathole

Remarks: Elev. 1496 Anhy 2615 = 2644
(If additional description is necessary, use BACK of this form.)

INVOICE RECEIVED 05-07-1990
did not observe this plugging.
Wichita, Kansas

DATE 5-9-90

INV. NO. 28098

Carl S.

Signed Carl Goodrow (TECHNICIAN)