

10-7

4-060443

TO: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API number: 15-193-20,615-00-00

E2 E2 MW /4 SEC. 32, 09 S, 31 W  
1980 feet from S section line  
2310 feet from E section line

Operator license# 9860 Lease Dechert well # 1

Operator: Castle Resources, Inc. County Thomas

Address: 1200 E. 27th. Street Well total depth 4670 feet  
Suite C Conductor Pipe: 0 inch @ 0 feet  
Hays, Kansas 67601 Surface pipe 8 5/8 Inch @ 265 feet

151.77

Aband. oil well \_\_, Gas well \_\_, Input well \_\_, SWD \_\_, D & A X

Plugging contractor: Emphasis Oil Operations License# 1993

Address: Rusell, Kansas 67665

Company to plug at: Hour: 6:00A.M. Day: 7 Month: October Year: 93

Plugging proposal received from: Jack Fox

Company: Emphasis Oil Operations Phone: \_\_\_\_\_

Were: Order 190 sxs. 60/40 posmix - 6% gel - 1/4# flocele per sx.  
Space all plugs with heavy drill mud through drill pipe.

Plugging Proposal Received by: Herb Deines  
Plugging operations attended by agent? All[ ], Part[ ], None[ X ]

Completed: Hour: 6:00A.M., Day: 7, Month: October, Year: 93

Actual plugging report:  
1st. plug at 2625' w/25 sxs. - Anhydrite 2614' - 2648'.  
2nd. plug at 1500' w/100 sxs.  
3rd. plug at 315' w/40 sxs.  
4th. plug at 40' w/10 sxs.  
Rathole with 15 sxs.

Remarks: Allied Cementing.  
Condition of casing(in hole): GOOD \_\_\_ BAD \_\_\_ Anhy.plug: YES X NO \_\_\_  
Bottom plug(in place): YES \_\_\_ , CALC \_\_\_ , NO X Dakota plug: YES X ,  
Plugged through TUBING \_\_\_ , CASING \_\_\_ . Elevation: 3036 GL

I did  and not  observe the plugging.

INVOICED

DATE 10-20-93  
INV. NO. 38988

RECEIVED  
STATE CORPORATION COMMISSION  
10-18-1993  
OCT 18 1993  
CONSERVATION DIVISION  
Wichita, Kansas  
Form CP-2/3  
DK (agent)