

11-22

6 070876

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 193-20,531-00-00  
SE SW NW, SEC. 25, T 9 S, R 33 W/EX

TECHNICIAN'S PLUGGING REPORT

Operator License # 5316

2970 feet from S section line

Operator Name & Address: Falcon Exploration Inc.

4290 feet from E section line

Address: 125 N. Market #1075

Lease Name Thorpe Well # 1

Address: Wichita, Ks. 67202

County Thomas 154.05

Address: Jim Thatcher

Well Total Depth 4740 feet

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 329

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A xx

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Blue Goose Drilling Co. License Number 5104

Address Box 1413 Great Bend, Ks. 67530

Company to plug at: Hour: AM Day 2 Month: Nov Year: 19 90

Plugging proposal received from Martin Miller

(company name) blue Goose Drilling (phone) \_\_\_\_\_

were: 8 5/8 329 s.p. cwc w/190 sks 60/40 poz 2% gel 3% ca cl.

By Allied. Miss Well. Elv. 3145. Anhy 2686. No circ problems. 44 vis. 9.5 weight-  
11. w.1. Proposal 190 sks 60/40 poz 6% gel 3% ca cl. Spot with drill stem; circ,  
heavy mud between all plugs. 25 sks at 2700 ; 100 sks w/ 1 sk f.c. at 1840; 40 sks  
at 370; 10 sks at 40; 15 sks in rathole, circ.

Plugging Proposal Received by *MJM* Marion J. Schmidt  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None xx

Operations Completed: Hour: 1:00 PM Day: 22 Month: Nov Year: 19 90

ACTUAL PLUGGING REPORT Blue Goose ordered 190 sks 60/40 poz 6% gel 3% ca cl.

Spotted with drill stem; circ; heavy mud between all plugs

1st plug at 2700 w/25 sks cement

2nd plug at 1840 w/100 sks cement and 1 sk f.c.

3rd plug at 370 w/40 sks cement

4th plug at 40 w/10 sks 15 sks in rathole. Cir.

Remarks: Allied Cementing  
(if additional description is necessary, use BACK of this form.)

INVOICED

DATE 12-14-90

INV. NO. 30259

*Jim S*

Signed *Marion J. Schmidt*  
(TECHNICIAN) Marion J. Schmidt

RECEIVED  
STATE CORPORATION COMMISSION  
DEC 10 1990  
12-10-1990  
CONSERVATION DIVISION  
Wichita, Kansas