

031386

7-9

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER IS- 193-20311-00-00  
NW SW NE SEC. 28 T 9 S. R 33 W/Ex

TECHNICIAN'S PLUGGING REPORT

Operator License # 5063

Operator: Energy Exploration Inc.  
Name & Address: 10002 S. Broadway  
Wichita, Ks. 67211

3630 feet from E section line  
2310 feet from E section line

Lease Name Herbel Well # 1

County Thomas 155.03

Well Total Depth 4770 feet

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 367

Abandoned Oil Well  Gas Well  Input Well  SMD Well  O&A

Other well as hereinafter indicated

Plugging Contractor Allied Cement License Number

Address Russell, Ks.

Company to plug at: Hour: PM Day: 9 Month: July Year: 1990

Plugging proposal received from Bill Luck

(company name) Energy Exp. Inc. (phone)

Remarks: 8 5/8' set at 367 w/240 sks cem. 4 1/2' set at 4768 w/250 sks

2 stage from 2364 w/450 sks cement blend. Order 200 sks

65/35 poz 10% gel 400 lbs. hulls. Allied Cement Co. Hensley

Water Trucks.

RECEIVED  
STATE CORPORATION COMMISSION  
07-17-1990  
CONSERVATION DIVISION  
Wichita, Kansas

Plugging Proposal Received by Carl Goodrow (TECHNICIAN)

Plugging Operations attended by Agent?: All  Part  None

Operations Completed: Hour: 1:30PM Day: 9 Month: July Year: 1990

ACTUAL PLUGGING REPORT Sq 4 1/2 w/145 sks cement blend w/500 lbs. hulls mixed into max

psi 1500 lbs. Close in psi 1000 lbs.

Test backside w/1 1/2 bbl slurry to max psi 400. lbs. Release to 0 lbs. psi.

Plug complete.

Remarks: (If additional description is necessary, use BACK of this form.)

INVOICED

DATE 7-24-90

INV. NO. 28706

J.G.S.

Signed Carl Goodrow (TECHNICIAN)

Carl Goodrow