

11-4

63
R

4- 060266

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,577-00-00

NW NW SE /4 SEC. 32, 09 S, 33 W
2310 feet from S section line
2310 feet from E section line

Operator license# 5135 Lease Lunsway well # 1

Operator: John O. Farmer, Inc. County Thomas

Address: P.O. Box 352 Well total depth 4771 feet
Russell, Kansas 67665 Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 368 feet

155.05

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Shields Drilling Company, Inc. License# 5655

Address: Russell, Kansas 67665

Company to plug at: Hour: 9:00P.M Day: 4 Month: November Year: 91

Plugging proposal received from: Burton Berry

Company: Shields Drilling Company, Inc. Phone: _____

Were: Order 200 sxs. 60/40 pos. - 6% gel. - 1/4# flocele per sx.
Space all plugs with heavy drilling mud through drill pipe.

Plugging Proposal Received by: Herb Deines

Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:00P.M, Day: 4, Month: November, Year: 91

Actual plugging report: _____

1st. plug at 2700' with 25 sxs. - Anhydrite 2698' - 2729'.

2nd. plug at 1885' with 100 sxs. - Dakota 1581' - 1881'.

3rd. plug at 420' with 40 sxs. - Surface pipe to 368'.

4th. plug at 40' with 10 sxs.

Rathole with 15 sxs.


Mousehole with 10 sxs.

Remarks: Halliburton Cementing.

INVOICED

RECEIVED

State Corporation Commission



DATE 12-4-91 NOV 14 1991

INV. NO. 33921 CONSERVATION DIVISION
Wichita, Kansas

Herb S.

(agent)
Form CP-2/3