

6 050327

77

API NUMBER 15- 193-20432-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

NE SE NE, SEC. 33, T 9 S, R 33 W/8
3630 feet from S section line
330 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5886

Lease Name Friesen Well # 1

Operator: Chief Drilling Co.

County Thomas 154.38

Name & Address 151 N. Main # 700

Well Total Depth 4750 feet

Wichita, Kansas 67202

Conductor Pipe: Size feet

Surface Casing: Size 8 5/8 feet 348

Abandoned Oil Well Gas Well Input Well SWD Well D&A X

Other well as hereinafter indicated

Plugging Contractor Warrior Drilling Co License Number 5883

Address Wichita, Kansas

Company to plug at: Hour: Day: Month: Year: 19

Plugging proposal received from Marion Burris

(company name) Warrior Drilling Co (phone)

were: Order 210 Lbs 60/40 poz mix-6% gel - 3% cal. Cl. 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Elv 3177 1600' = 1577' + 300' = 1877

Anhy 2712 to 2744

Plugging Proposal Received by (TECHNICIAN)

Plugging Operations attended by Agent?: All Part None X

Operations Completed: Hour: 3:30PM Day: 19 Month: March Year: 19 87

ACTUAL PLUGGING REPORT

1st plug @ w/ sks. Allied

2nd plug @ 2720 w/ 25 sks

3rd plug @ 1900 w/100 sks 1 sac flo cel

4th plug @ 360 w/ 40 sks

5th plug @ 50 w/8 5/8 sks Plug 10 sx

Remarks: 15 sks in Rat Hole 10 sks in Mouse Hole

(If additional description is necessary, use BACK of this form.)

(XXX) (do not) observe this plugging.

DATE Cemented by: Allied Cementing Co.

Signed Gilbert P. Lenker (TECHNICIAN)

INV. NO. 16587

RECEIVED
MAY 17 1987
STATE CORPORATION COMMISSION

RECEIVED
MAY 17 1987
04-17-1987
CONSERVATION DIVISION
Wichita, Kansas

INVOICED