

4-032354

2-12

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Number: 15-193-20,545-00-00

NE NW SE /4 SEC. 33, 09, 33 W
2310 feet from S section line
1650 feet from E section line

Operator license# 4629

Lease: Dumler Well # 1-33

Operator: Brito Oil Company, Inc.

County: Thomas 154.05

Address: 120 S. Market - Suite #400
Wichita, Kansas 67202

Well total depth 4740 feet
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 383 feet

Aband. oil well X, Gas well , Input well , SWD , D & A

Plugging contractor: Poe Services, Inc. License# 3152

Address: Oberlin, Kansas 67749

Company to plug at: Hour: A.M. Day: 12 Month: February Year: 1999

Plugging proposal received from: Brito

Company: Brito Oil Company, Inc. Phone:

Were: Order 325 sxs 60/40 pozmix - 10% gel - 500# hulls.
Allied Cement Company.

RECEIVED
KANSAS CORP COM
1999 FEB 26 A 11:2
02-26-1999

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[X], Part[], None[]

Completed: Hour: 12:00 P.M., Day: 12 Month: February, Year: 1999

Actual plugging report: 8 5/8" set at 383' w/180 sxs cwc. 5 1/2" set at 4738' w/200 sxs.
Prod. Perfs 4301' - 4333'. Port collar set at 2665' w/300 sxs cwc. PBTB 4321'.
CIBP at 4321'. Squeezed 5 1/2" with 340 sxs cement blend with 600# hulls mixed into Max.
P.S.I. 500#. S.I.P. 500#.

Topped off 8 5/8" with 10 sxs cement blend. Cement at surface. Plug complete.

Remarks:

Condition of casing(in hole): GOOD BAD Anhy.plug: YES X NO

Bottom plug(in place): YES , CALC , NO Dakota plug: YES X, NO

Plugged through TUBING , CASING . Elevation: GL

I did[X] / did not[] observe the plugging.

Carl Goodrow
(agent)

NO.

INVOICED

DATE 3-1-99

INV. NO. 60666