

8-16

295
R

6 070942

API NUMBER 15- 193-20,564-00-00

To: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING SECTION
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

SW SW NE, SEC. 33, T 9 S, R 33 W E
2970 feet from S section line
2310 feet from E section line

TECHNICIAN'S PLUGGING REPORT
Operator License # 4629

Operator: Brito Oil Company, Inc.
Name & Address 200 E. First, Suite 208
Wichita, Kansas 67202
Raul F. Brito

Lease Name Friesen Well # 1-33
County Thomas 154.70
Well Total Depth 4760 feet
Conductor Pipe: Size _____ feet
Surface Casing: Size 8 5/8 feet 364

Abandoned Oil Well _____ Gas Well _____ Input Well _____ SWD Well _____ D&A X
Other well as hereinafter indicated _____

Plugging Contractor Blue Goose Drilling License Number 5104

Address Box 1413, Great Bend, Kansas 67530

Company to plug at: Hour: P.M. Day: 16th Month: August Year: 19 91

Plugging proposal received from Mark Muller

(company name) Blue Goose Drilling, Inc. (phone) 316-263-8787

were: 8 5/8" S.P. 364' cw w/200 sx. 60/40 Pozmix - 2% Gel. - 3% C.C. By Allied.

Miss Well. Elv. 3175'. Anhy. 2701'. Mud condition 45 vis. 9.5 Wt. 10.0 W.L.

Proposal circulate hole. 200 sx. 60/40 pozmix - 6% Gel. w/1 sx. Flocele.

Spot with drill Stem. Heavy mud between all plugs. 25 sx. @ 2710' - 100 sx. w/1 sx. Flocele @ 1875' - 50 sx. @ 410' - 10 sx. @ 40' - 15 sx. in Rathole (circulate)

Plugging Proposal Received by Marion J. Schmidt
(TECHNICIAN)

Plugging Operations attended by Agent?: All _____ Part _____ None X

Operations Completed: Hour: 2:30 P.M. Day: 16th Month: August Year: 19 91

ACTUAL PLUGGING REPORT Brito ordered 200 sx. 60/40 Poz. - 6% Gel. - 3% C.C. -

1 sx. Flocele. Circulated hole. Spotted cement through drill stem. Heavy mud between all plugs.

1st plug @ 2710' w/25 sx. cement. 4th plug @ 40' w/10 sx. cement.

2nd plug @ 1875' w/100 sx. cement w/1 sx. F.C. 15 sx. in Rate Hole (Circulated)

3rd plug @ 410' w/50 sx. cement.

Remarks: Cement By: Allied.

RECEIVED
STATE CORPORATION COMMISSION
08-29-1991
AUG 29 1991

(If additional description is necessary, use BACK of this form.)

(XXXXX did not) observe this plugging.

DATE 9-11-91
INV. NO. 33064

Rub. S.

Signed Marion J. Schmidt
(TECHNICIAN)
Conservation Division
Wichita, Kansas