

4-031666

2-27

208
R

TO:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,588 00-00

SE NW SE /4 SEC. 33 , 09 S, 33 W
1650 feet from S section line
1650 feet from E section line

Operator license# 4629

Lease Dumler well #2-33

Operator: Brito Oil Company, Inc.

County Thomas

Address: 200 E. 1st Street
Suite 208
Wichita, Kansas 67202

Well total depth 4730 feet ^{153.72}
Conductor Pipe: 0 inch @ 0 feet
Surface pipe 8 5/8 Inch @ 367 feet

Aband. oil well , Gas well , Input well , SWD , D & A X

Plugging contractor: Blue Goose Drilling License# 5104

Address: _____

Company to plug at: Hour: P.M. Day: 27 Month: February Year: 92

Plugging proposal received from: Martin Miller

Company: Blue Goose Drilling Phone: _____

Were: 8 5/8" set @ 367' cwc. Order 190 sx. 60/40 pozmix - 6% gel. - 3% c.c. Allied Cement Company.

Plugging Proposal Received by: Carl Goodrow

Plugging operations attended by agent? All[], Part[], None[X]

Completed: Hour: 10:30P.M., Day: 27, Month: Februrary, Year: 92

Actual plugging report: _____

Spot cement plugs with drill pipe.

1st. plug @ 2700' w/ 25 sx.

2nd. plug @ 1850' w/100 sx. with hulls.

3rd. plug @ 420' w/ 40 sx.

4th. plug @ 40' w/ 10 sx. W.P.

Circ. 15 sx. in Rathole.

RECEIVED
STATE CORPORATION COMMISSION
APR 8 1992
04-03-1992
CONSERVATION DIVISION
Wichita, Kansas

Remarks: Elev. 3167' - Anhy. 2675' - 2707'

Condition of casing(in hole):GOOD X BAD Anhy.plug:YES X NO

Bottom plug(in place):YES , CALC , NO Dakota plug:YES X, NO

Plugged through TUBING , CASING . Elevation: 3167 GL

I did[] / did not[X] observe the plugging.

Carl Goodrow

DATE 4-8-92

(agent)

INV. NO. 34907