

9-5

300
R

6-010764

TR:
STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
200 COLORADO DERBY BUILDING
WICHITA, KANSAS 67202

API number: 15-193-20,560-00-00
SE /4 SEC. 15, 9 S, 34 W
1320 feet from S section line
1320 feet from E section line

Operator license# 4197 Lease Kelly well # 1-15

Operator: Dunne Oil Company County Thomas

Address: 100 S. Main Well total depth 4890 feet 158.92
Suite 410 Conductor Pipe: 0 inch @ 0 feet
Wichita, Kansas 67202 Surface pipe 8 5/8 Inch @ 303 feet

Aband. oil well , Gas well , Input well , SWD , D & A

Plugging contractor: Murfin Drilling License# 6033

Address: Wichita, Kansas 67202

Company to plug at: Hour: _____ Day: 4th Month: September Year: 91

Plugging proposal received from: Rodney Farr

Company: Murfin Drilling Phone: _____

Were: Order 200 sx. cement - 60/40 pozmix - 6% gel. - 2 sx. flocele.
Heavy mud between all plugs. Pump cement down drill pipe.
Elevation 3229' - Anhydrite 2785' - 2813' - Arbuckle - No.
Top Dakota 1700' - 1529' - 1829'.

Plugging Proposal Received by: Dale F. Balthazor
Plugging operations attended by agent? All , Part , None

Completed: Hour: 9:00A.M., Day: 5th, Month: September, Year: 91

Actual plugging report:
1st plug 25 sx. @ 2810'.
2nd plug 100 sx. @ 1830'.
3rd plug 40 sx. @ 330'.
4th plug 10 sx. @ 40'.
15 sx. in Rathole.
10 sx. in Mousehole.

RECEIVED
KANSAS CORPORATION COMMISSION
OCT 8 1991
10-08-1991
CONSERVATION DIVISION
WICHITA, KS

Remarks: Cementing Company: Allied.

I did and observe the plugging.

DATE 10-16-91
INV. NO. 33358

Rob. S.

Dale F. Balthazor