

TO: STATE CORPORATION COMMISSION
CONSERVATION DIVISION - PLUGGING
130 SOUTH MARKET, SUITE 2078
WICHITA, KANSAS 67202

API Well Number: 15-193-20216-00-00
Spot: W2NW Sec/Twnshp/Rge: 5-9S-36W
3960 feet from S Section Line, 4620 feet from E Section Line
Lease/Unit Name: PALMGREN B Well Number: 1
County: THOMAS Total Vertical Depth: 4800 feet

Operator License No.: 31514
Op Name: THOROUGHbred ASSOCIATES L.L.C.
Address: 8100 E. 22ND ST. - BUILDING 600
WICHITA, KS 67226

Production Casing Size: 2.875 feet: 753 180 SX CMT
Surface Casing Size: 8.625 feet: 280 200 SX CMT

#156

Well Type: GAS UIC Docket No: _____ Date/Time to Plug: 07/23/2003 4:00 PM

Plug Co. License No.: 99998 Plug Co. Name: COMPANY TOOLS

Proposal Rcvd. from: CINDA SARIA Company: THOROUGHbred ASSOCIATES LL Phone: (316) 685-1512

Proposed Plugging Method: Ordered 250 sxs 60/40 pozmix - 10% gel.
Top down plug through 2 7/8" production casing.
Connected to 8 5/8" surface casing - squeeze with cement.

Plugging Proposal Received By: HERB DEINES

Witness Type: Plugging Operations 100% Witnessed (Complete)

Date/Time Plugging Completed: 07/23/2003 4:40 PM

KCC Agent: DARREL DIPMAN

Actual Plugging Report:

T.D. 4800'. PBTD 722'. Perfs 684' - 698'.
S.P. set at 280' w/200 sxs. Production casing set at 753' w/180 sxs.
Connected to 2 7/8" production casing. Pumped 80 sxs cement with 200# hulls.
Max. P.S.I. 1000#. S.I.P. 1000#.
Connected to 8 5/8" surface casing. Pumped .25 bbls water.
Max. P.S.I. 700#.

RECEIVED
07-30-2003
JUL 30 2003

KCC WICHITA

Remarks: ALLIED CEMENTING COMPANY.

Plugged through: CSG

District: 04

Signed Darrel Dipman
(TECHNICIAN)

INVOICED

DATE 7-30-03

INV. NO. 2004060276

JUL 24 2003

ABRAXAS PETROLEUM CORP
P.O. BOX 17485

#1 PALMGREN "B"

5-9-36W
C. W/2 NW

SAN ANTONIO, TX 78217

CONTR RAINS & WILLIAMSON CITY THOMAS

GEOL GLENN TRACEY FIELD WC(3/4 SW OF STUDER)

E 3427 KB CM 12/2/80 CARD ISSUED 3/19/81 IP SIGW

API 15-193-20,216

NIOB 665-67 &
684-698

LOG	TOPS	DEPTH	DATUM
NIOB		NA	
ANH		2895	+ 532
B ANH		2926	+ 501
HEEB		4162	- 735
LANS		4210	- 783
B KC		4500	- 1073
MARM		4536	- 1109
PAW		4620	- 1193
FT SC		4660	- 1233
CHER		4672	- 1245
LTD		4803	- 1376
RTD		4800	- 1373

8 5/8" 280/200sx, 2-7/8" TBC 753/180sx

MIGT - CO, P8TD 722, RF 56/684-698
10/665-667, ERAC 46,000 CF NITRO
2250 GAL FOAM & 10,000#SD, ST, POT
NA

INDEPENDENT OIL & GAS SERVICE
WICHITA, KANSAS

KCC
JUL 29 2003
HAYS, KS



THOROUGHBRED ASSOCIATES

RECEIVED
AUG 18 2003
KCC WICHITA

August 8, 2003

Kansas Corporation Commission
130 S. Market, Room 2078
Wichita, Kansas 67202

RE: API #15-193-20216-00-00
Palmgren B #1
4620'FSL; 4620'FEL
C NW NW
Sec. 5-T9S-R36W
Thomas County, Kansas

Dear Sirs:

Enclosed herewith are the following for the above-captioned well:

- (1) One copy of Well Plugging Record
- (2) One copy of cementing job

Please hold the information pertaining to this well confidential for one year. If you should need any additional information, please do not hesitate to call.

Sincerely,

THOROUGHBRED ASSOCIATES

Cinda Garcia