

6 031530

API NUMBER 15-193-20244-00-00

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

NE SW \_\_\_\_\_, SEC. 35, T 9 S, R 36 W/E  
1980 feet from S section line  
3300 feet from E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 4767  
Operator: Ritchie Exp Inc.  
Name & Address: 125 N. Market #1000  
Wichita, Ks. 67202

Lease Name Shalz Well # A #1  
County Thomas 160.87  
Well Total Depth 4950 feet  
Conductor Pipe: Size \_\_\_\_\_ feet  
Surface Casing: Size 8 5/8 365 feet

Abandoned Oil Well  Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A \_\_\_\_\_

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Kelso Casing Pulling License Number 6050  
Address Chase, Ks.

Company to plug at: Hour: AM Day: 23 Month: April Year: 19 91

Plugging proposal received from Monte

(company name) Kelso (phone) \_\_\_\_\_

were: 8 5/8 set at 365 w/275 sks. 4 1/2 set at 4754 w/200 sks. PBDT 4738 toc 3750.

Perf 4370 - 4707. Order sand and common cement: Pull pipe order

225 sks 65/35 poz 10% gel, 500 lbs. hulls. Allied Cement Co. Hoxie Tank Service.

Ran wireline weight to 2200. Hole open small bridge at 1250.

Plugging Proposal Received by Carl Goodrow  
(TECHNICIAN)

Plugging Operations attended by Agent?: All  Part \_\_\_\_\_ None \_\_\_\_\_

Operations Completed: Hour: 10:15AM Day: 23 Month: April Year: 19 91

ACTUAL PLUGGING REPORT Sand back to 4320 w/4 sks common cement on sand w/bailer.

One shot recovered 3000 of 4 1/2 casing. Sq 8 5/8 w/225 sks cement blend w/500 lbs. hulls

mixed in to max psi 500 lbs. Close in psi 200 lbs. Plug complete.

RECEIVED  
STATE CORPORATION COMMISSION

JUN 07 1991  
06-07-1991  
CONSERVATION DIVISION  
Wichita, Kansas

Remarks: (If additional description is necessary, use BACK of this form)

INVOICED  
(If additional description is necessary, use BACK of this form) observe this plugging.

DATE 6-18-91  
INV. NO. 32171

Sub. S

Signed Carl Goodrow  
(TECHNICIAN)  
Carl Goodrow