

To: STATE CORPORATION COMMISSION  
CONSERVATION DIVISION - PLUGGING SECTION  
200 COLORADO DERBY BUILDING  
WICHITA, KANSAS 67202

API NUMBER 15- 163- 22,437 -00-00  
E 1/2 SE NW Sec. 4, T 10 S, R 16 (W)  
\_\_\_\_\_ feet from N/S section line  
\_\_\_\_\_ feet from W/E section line

TECHNICIAN'S PLUGGING REPORT

Operator License # 5005

Lease Name Conger Well # 1

Operator: Sunburst Exp  
Name & 125 N. Emporia  
Address Wichita, Ks. 67202

County Rooks

Well Total Depth 3550 feet 115.38

Conductor Pipe: Size 0 feet

Surface Casing: Size 8 5/8 feet 303

Abandoned Oil Well \_\_\_\_\_ Gas Well \_\_\_\_\_ Input Well \_\_\_\_\_ SWD Well \_\_\_\_\_ D&A XX

Other well as hereinafter indicated \_\_\_\_\_

Plugging Contractor Thunderbird Drilling Company License Number 5131

Address Box 18407, Wichita, Ks.

Company to plug at: Hour: PM Day: 16 Month: August Year: 19 84

VERBAL PLUGGING ORDERS GIVEN TO Ed Cook

(company name) \_\_\_\_\_ (phone) \_\_\_\_\_

were: Order 210 sks 50/50 pozmix 6% gel 3% cal. cl. 1 sk flo-cel and 8 5/8" plug.

Spot with drill pipe with no less than 36 vis. mud between all plugs, with good circulation and no fluid loss.

Signed \_\_\_\_\_  
(TECHNICIAN)

Plugging Operations attended by Agent?: All \_\_\_\_\_ Part \_\_\_\_\_ None XX

Operations Completed: Hour: 4 AM Day: 17 Month: August Year: 19 84

ACTUAL PLUGGING REPORT

1st plug @ 3520 w/25 sks

2nd plug @ 1210 w/25 sks

3rd plug @ 680 w/100 sks 1 sk flo cel

4th plug @ 340 w/40 sks

5th plug @ 40 w/8 5/8" plug 1/2 sk hulls 10 sk

10 sks in Rat Hole

Cemented by Allied

Remarks: \_\_\_\_\_

RECEIVED  
STATE CORPORATION COMMISSION  
08-27-1984  
AUG 27 1984

CONSERVATION DIVISION  
Wichita, Kansas

I hereby certify that the above plugging instructions were given as herein stated and that I (~~did~~ / did not) observe this plugging.

Signed Gilbert P. Leiker  
(TECHNICIAN)

INVOICED

DATE 8-29-84

INV. NO. 3463

8-17

8-24-84  
26