



State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

P.O. Box 17027 3830 S. Meridian  
WICHITA, KANSAS 67217

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

RECEIVED  
STATE CORPORATION COMMISSION  
JAN 26 1973  
01-26-1973  
CONSERVATION DIVISION  
Wichita, Kansas

J. Lewis Brock  
Administrator  
500 Insurance Building  
Wichita, Kansas 67202

15-065-20583-00-00

Dear Sir:

Mr. Elmer Zimmerman of Woodman-Iannitti Drlg., Co., has this date requested permission to plug the following described well:

Mr. Zimmerman guarantees payment of the plugging fee.

Operator's full Name: National Oil Company,

Complete Address: Garvey Building, Wichita, Kansas.

Lease Name: Acheson Well No. 1

Location: SE-SW-SE Sec. 21 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3828' Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Zimmerman was instructed to plug the well as follows:

223'--8 5/8" Surface casing, cement circulated with 135 Sx.  
Top of Dakota section @ 575'.

Circulate hole with heavy mud. Pull DP to 800' and displace 110 Cu. Ft. cement thru DP. Pull DP to 245' and displace 30 Cu. Ft. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Cu. Ft. cement to bottom of cellar.

Very truly yours,

Conservation Division Agent