

State of Kansas



ROBERT B. DOCKING Governor  
 DALE E. SAFFELS Chairman  
 JULES V. DOTY Commissioner  
 JAMES O. GREENLEAF Commissioner  
 RAYMOND B. HARVEY Secretary  
 JACK GLAVES Gen. Counsel

State Corporation Commission

CONSERVATION DIVISION

(Oil, Gas and Water)

500 Insurance Bldg.

212 N. Market

WICHITA, KANSAS 67202

VERBAL PERMIT FORM  
(To Be Filed By Plugging Agent)

15-065-20194-00-00

RECEIVED  
 STATE CORPORATION COMMISSION  
 DEC 30 1968  
 CONSERVATION DIVISION  
 Wichita, Kansas

12-30-1968

J. Lewis Brock  
 Administrator  
 500 Insurance Building  
 Wichita, Kansas 67202

Dear Sir:

Mr. Ronnie Parks of Gabbert-Jones, Incorporated, has this date requested permission to plug the following described well:

Mr. Parks guarantees payment of the plugging fee.

Operator's full Name: Robinowitz Oil Company,

Complete Address: 1322 East 50th, Tulsa, Oklahoma.

Lease Name: Lowell Well No. 3

Location: SW-NE-NW Sec. 27 Twp. 10 Rge. (E)(W) 21

County: Graham Total Depth 3812 Oil Well

Gas Well  Input Well  SWD Well  D & A X Lost Hole

Mr. Parks was instructed to plug the well as follows:

246'--8 5/8" Surface casing, cement circulated with 150 Sx.  
Top of Dakota section @ 650'.

Circulate hole with heavy mud. Pull DP to 875' and displace 100 Sx. cement thru DP. Pull DP to 275' and displace 20 Sx. cement thru DP. Pull DP, set bridge @ 40' with 1/2 sack hulls and 10 Sx. cement to bottom of cellar.

Very truly yours,

M. L. Fisher  
 Conservation Division Agent